


Redline Gauge Glass




Cleaning Brushes

Product Description

Redline gauge glass is typically used in low pressure boilers, reservoirs, and tank applications. Redline gauge glass features a red stripe and a white stripe. In the presence of a colourless fluid the red and white line magnifies and highlights the fluid level.



Pressure ratings vary depending on diameter, thickness, and environment.

Part Numbers:



Example: SGP 12 \times 18 REDLINE - Redline Gauge Glass, 1/2" O.D., 18" Length

Redline Gauge Glass



Redline Gauge Glass

Part Number	O.D.	Wall Thickness	Length	Max. Recommended Working Pressure (PSI)	
				Temp. Up to 66°C No Corrosion	Temp. Up to 218°C Steam Boiler Service
SGP 12x8REDLINE	1/2 +0, -1/32	5/64 +/- 1/64	8	390	300
SGP 12x10REDLINE			10	370	295
SGP 12x12REDLINE			12	360	295
SGP 12x14REDLINE			14	345	290
SGP 12x18REDLINE			18	325	280
SGP 12x20REDLINE			20	310	280
SGP 12x24REDLINE			24	280	270
SGP 12x30REDLINE			30	250	N/R
SGP 12x36REDLINE			36	215	N/R
SGP 12x48REDLINE			48	175	N/R
SGP 12x60REDLINE			60	135	N/R
SGP 12x72REDLINE			72	100	N/R
SGP 58x8REDLINE	5/8 +0, -1/32	3/32 +/- 1/64	8	370	285
SGP 58x10REDLINE			10	345	280
SGP 58x12REDLINE			12	335	280
SGP 58x14REDLINE			14	325	275
SGP 58x16REDLINE			16	315	270
SGP 58x18REDLINE			18	305	265
SGP 58x20REDLINE			20	290	265
SGP 58x24REDLINE			24	265	255
SGP 58x30REDLINE			30	235	N/R
SGP 58x36REDLINE			36	205	N/R
SGP 58x48REDLINE			48	165	N/R
SGP 58x60REDLINE			60	125	N/R
SGP 58x72REDLINE	72	90	N/R		
SGP 34x8REDLINE	3/4 +0, -1/32	7/64 +/- 1/64	8	360	280
SGP 34x10REDLINE			10	340	275
SGP 34x12REDLINE			12	330	275
SGP 34x14REDLINE			14	320	270
SGP 34x16REDLINE			16	310	265
SGP 34x18REDLINE			18	300	260
SGP 34x20REDLINE			20	285	260
SGP 34x22REDLINE			22	270	250
SGP 34x24REDLINE			24	260	250
SGP 34x30REDLINE			30	230	N/R
SGP 34x36REDLINE			36	200	N/R
SGP 34x48REDLINE			48	160	N/R
SGP 34x60REDLINE	60	125	N/R		
SGP 34x72REDLINE	72	90	N/R		
SGP 78x30REDLINE	7/8 +0, -1/32	1/8 +/- 1/32	30	240	N/R
SGP 78x48REDLINE			48	185	N/R
SGP 78x72REDLINE			72	100	N/R
SGP 1x24REDLINE	1 +0, -1/32	1/8 +/- 1/32	24	230	N/R
SGP 1x30REDLINE			30	210	N/R
SGP 1x36REDLINE			36	195	N/R

N/R – Not Recommended